

## Workplace Health and Safety Queensland

## 4. Concrete pumping—clean out procedures

Cleaning out concrete pumping equipment can be a highly hazardous operation if correct safety procedures are not used. When air is used to clean out lines, the risk will generally be greater.



### Always remember to:

- Clean out in an area set aside for this particular activity.
- Exclude people not involved in the clean out procedure from the work zone.
- Ensure the pipeline is secured to withstand extra forces during the clean out process.

- Ensure the pipeline is fitted with a dump valve vented to atmosphere when cleaning with air. The dump valve should be larger than the air supply valve.
- Place concrete waste product and water in specified areas where people will not be at risk.

### Never:

- Clean out pipelines with air unless the rubber hose has been removed from the end of the pipeline.
- Clean out pipelines with air unless the end of the pipeline is fitted with a ball catcher or all material is blown into a receptacle that contains all spray and projectiles.
- Release the ball catcher unless compressed air has been dumped from the pipeline.
- “Shoot” the clean out plug from the end of the concrete line.

### More information

Further information is available from [www.worksafe.qld.gov.au](http://www.worksafe.qld.gov.au) or by calling the WHS Infoline on 1300 369 915.

© The State of Queensland (Department of Justice and Attorney-General) 2011

Copyright protects this document. The State of Queensland has no objection to this material being reproduced, but asserts its right to be recognised as author of the original material and the right to have the material unaltered.

The material presented in this publication is distributed by the Queensland Government as an information source only. The State of Queensland makes no statements, representations, or warranties about the accuracy or completeness of the information contained in this publication, and the reader should not rely on it. The Queensland Government disclaims all responsibility and all liability (including, without limitation, liability in negligence) for all expenses, losses, damages and costs you might incur as a result of the information being inaccurate or incomplete in any way, and for any reason.

Workplace Health and Safety Queensland, Department of Justice and Attorney-General

FACT SHEET – Concrete pumping plant issues  
PN10127 Version 1. Last updated 29 July 2009.